

Historic, Archive Document

Do not assume content reflects current scientific knowledge, policies, or practices.

Reserve
aTC424
.M5F56

LOOD PLAIN MANAGEMENT STUDY

CLAM RIVER WEXFORD COUNTY, MICHIGAN

JULY 1987



prepared by:

**U.S. Department of Agriculture
Soil Conservation Service
East Lansing, Michigan**

in cooperation with:

**Michigan Department of Natural
Resources
Cherry Grove, Clam Lake, Haring
and Selma Townships, City of
Cadillac and Wexford County
Wexford County Soil Conservation
District**

AD-83 Bookplate
(1-48)

NATIONAL

**A
G
R
I
C
U
L
T
U
R
A
L**



LIBRARY

FOREWORD

This report defines the flood characteristics of the Clam River, Lake Cadillac, Lake Mitchell and Pleasant Lake located in Wexford County, Michigan. Development exists within the flood plain and can be expected to increase in the future.

This cooperative report was prepared for the guidance of local officials in planning the use and regulation of the flood plain. Four potential floods are used to represent the degrees of major flooding that may occur in the future. These floods, the 10-year, 50-year, 100-year and 500-year, are defined in the report and should be given appropriate consideration in future planning for safety of development in the flood plain. Over 6.6 miles of high water profiles along the Clam River show the expected flood elevations and water depths relative to the stream bed and flood plain. The 100-year and 500-year potential floods, in addition to flood prone areas around Lake Cadillac and Lake Mitchell, are further defined by flood hazard area photomaps that show the approximate areas that would be flooded.

Flood hazard area photomaps and high water profiles are based on existing conditions of the basin, stream and valley when the report was prepared.

Information in this report does not imply any federal authority to zone or regulate the use of flood plains; this is a state and local responsibility. This report provides a suitable basis for adoption of land use controls to guide flood plain development, thereby preventing intensification of flood losses.

Technical documentation for this study is on file with the Soil Conservation Service-USDA, 1405 South Harrison Road, East Lansing, Michigan 48823 (telephone 517-337-6612) and the Land and Water Management Division, Michigan Department of Natural Resources, Mason Building, P.O. Box 30028, Lansing, Michigan 48909.

Assistance and cooperation of the U.S. Geological Survey; Wexford County Soil Conservation District; city of Cadillac; Cherry Grove, Clam Lake, Haring and Selma Townships; and the Michigan Department of Natural Resources in the preparation of this report is greatly appreciated.

U.S. DEPT. OF AGRICULTURE
NATIONAL AGRICULTURAL LIBRARY

CATALOGING = PREP

CONTENTS

	<u>Page</u>
FOREWORD	i
CONTENTS AND APPENDICES	ii
LIST OF FIGURES AND TABLES	iii
INTRODUCTION	1
DESCRIPTION OF STUDY AREA	4
Watershed Area	4
Study Area Flood Plain	5
NATURAL VALUES	7
FLOOD PROBLEMS	9
EXISTING FLOOD PLAIN MANAGEMENT	11
ALTERNATIVES FOR FLOOD PLAIN MANAGEMENT	12
Present Condition	12
Land Treatment	12
Preservation and Restoration of Natural Values	13
Non-Structural Measures	15
Structural Measures	15
ALTERNATIVES FOR FLOOD PRONE AREAS	16
Present Condition	16
Preservation of Natural Areas	16
Non-Structural Measures	16
Structural Measures	16

APPENDICES

APPENDIX A - Flood Hazard Photomaps and High Water Profiles
APPENDIX B - Typical Valley Cross-Sections
APPENDIX C - Flood Discharges and Elevations
APPENDIX D - Investigations and Analyses
APPENDIX E - Bench Mark Descriptions
APPENDIX F - Glossary
APPENDIX G - Bibliography

LIST OF FIGURES

<u>No.</u>	<u>Title</u>	<u>Page</u>
1	Flood Hazard Study Area Map	6
2	Flood Hazard Photomaps Index Sheet, High Water Profiles and Flood Plain Delineations	Appendix A
3	Bench Mark Location Map	Before E-1

LIST OF TABLES

<u>No.</u>	<u>Title</u>	<u>Page</u>
1	Flood Discharges	Appendix C-1
2	Flood Elevations at Sections	Appendix C-2

FLOOD PLAIN MANAGEMENT STUDY

CLAM RIVER

WEXFORD COUNTY, MICHIGAN

INTRODUCTION

The flood plains of rivers, lakes and streams have been formed by nature to provide for the conveyance of flood flows resulting from large amounts of snowmelt and rainfall. Floods are acts of nature which cannot be wholly prevented by man. Therefore, the long-term solution to reducing flood damage and loss of life is to keep the flood plain void of development which could be damaged or which could obstruct the conveyance of flood waters. There are three basic actions which can be used to assure that flood plain areas are kept open:

1. Provide public information to make lending institutions and prospective property buyers aware of the flood hazards.
2. Initiate flood plain regulations to prevent the development of the flood plain in a manner which would be hazardous during floods.
3. Acquisition of flood prone areas for use as parks, open space, wildlife habitat and other public uses.

Potential users of the flood plain should base their decisions upon the advantages and disadvantages of such a location. Knowledge of flood hazards is not widespread and, consequently, the managers, potential users and occupants cannot always accurately assess the risks. In order for flood plain management to be effective in the planning, development and use of flood plains, it is necessary to:

1. Develop appropriate technical information and interpretations for use in flood plain management.
2. Provide technical services to managers of flood plain property for community, recreational, industrial and agricultural uses.
3. Improve basic technical knowledge about flood hazards.

Two Michigan state laws provide the Michigan Department of Natural Resources the responsibility and the authority to regulate all development in the flood plain areas.

Act 288, Public Acts of 1967, establishes minimum standards for subdividing land and for new development for residential purposes within flood plain areas. This act requires that preliminary plats be submitted to the Land and Water Management Division, Michigan Department of Natural Resources for review and determination of flood plain limits. Upon completion of review and establishment of the 100-year frequency flood plain limits, the preliminary plat may be approved and minimum building requirements specified.

Act 245, Public Acts of 1929 as amended by Act 167, Public Acts of 1968, requires that a permit be obtained from the Land and Water Management Division, Michigan Department of Natural Resources before filling or otherwise occupying the flood plain or altering any channel or watercourse in the state. The purpose of this control is to assure that the channels and the portion of the flood plain that are the floodways are not inhabited and are kept free and clear of interference or obstruction which will cause undue restriction of flood carrying capacities.

Requirements established by the Michigan Department of Natural Resources for occupation and development of flood plain areas under Acts 288 and 245 are intended to be minimum requirements only. The Department urges local units of government to adopt reasonable regulations which can be used to guide and control land use and development in flood hazard areas.

The Soil Conservation Service, United States Department of Agriculture carries out flood plain management studies under the authority of Section 6 of Public Law 83-566, in response to Recommendation 9(c), "Regulations of Land Use", of House Document No. 465, 89th Congress, 2nd Session and in compliance with Executive Order 11988, dated May 24, 1977. Flood plain management studies are carried out in accordance with Federal Level Recommendation 3 of "A Unified National Program for Flood Plain Management". The Soil Conservation Service and the Michigan Department of Natural Resources have agreed to carry out flood plain management studies in Michigan under provisions of the 1982 Joint Coordination Agreement. Priorities regarding location and extent of such studies in Michigan have been set in cooperation with the Michigan Department of Natural Resources.

The Wexford County Soil Conservation District; city of Cadillac; Cherry Grove, Clam Lake, Haring and Selma Townships; and the Michigan Department of Natural Resources (Sponsors) believed that a flood plain management study was needed for the Clam River, Lake Cadillac, Lake Mitchell and Pleasant Lake due to urbanization and the flooding problems that have already occurred. The Sponsors have determined that there is an increasing need to properly plan for the preservation and use of the flood plain in their urban and rural areas. They have indicated a need to develop technical information along the Clam River, Lake Cadillac, Lake Mitchell and Pleasant Lake to develop effective management programs.

The Sponsors have adopted resolutions indicating they intend to use the technical information from the flood plain management study as a basis for adopting zoning regulations, health and building codes, subdivision control regulations and such other regulations that may be needed to preserve the environmental quality of their natural resources, and to protect the health, safety, welfare and well-being of the citizens of their communities.

A request for a flood plain management study was made by the Sponsors and a plan of work, dated April 1985, was agreed to by the Sponsors, along with the Soil Conservation Service. Financial contributions for this study were made by the Sponsors and the Soil Conservation Service. The Wexford County Soil Conservation District will assist the other Sponsors with public information dissemination.

The Sponsors provided money for aerial photography for flood plain delineation uses and for watershed modeling purposes. They also furnished assistance to the Soil Conservation Service in gathering basic data. In addition, they also provided input to identify and select appropriate flood plain management alternatives.

The Land and Water Management Division, Michigan Department of Natural Resources provided coordination services with respect to study area discharges and hydraulics. They reviewed the technical aspects of the study and concurred with study results, as applicable, to implement various state statutes through the Federal Flood Insurance Program.

Natural flood plain values were obtained by Soil Conservation Service field people. Aerial photos and field checks were used to identify and delineate wetland areas. Topographic maps, planning commission data and communications with government officials were used to determine land use and development trends. Soils information was obtained from the published soil survey report for Wexford County.

Historic and archaeological data were obtained from township and county historians. Fishery management information was obtained from Michigan Department of Natural Resources field people.

In addition to flood prone areas, two floods are delineated, the 100-year and the 500-year frequency events. These floods have an average occurrence of once in the number of years as indicated; e.g. the 100-year flood occurs once in 100 years on the average. The 100-year flood has a one percent chance of being equaled or exceeded in any given year. In addition to flood prone areas and the two floods delineated on the aerial photomaps, the 10-year and 50-year floods are also shown on the high water profiles. The flood plain management program enacted by local action is to be based on the technical results and recommendations of this report.

The Land and Water Management Division, Michigan Department of Natural Resources and the Soil Conservation Service-USDA will, upon request, provide technical assistance to federal, state and local agencies and organizations in the interpretation and use of the information developed in this study. For assistance contact:

Wexford County Soil Conservation District
3060 West 13th Street
Cadillac, Michigan 49601-9658
Telephone: (616) 775-7422

DESCRIPTION OF STUDY AREA

Watershed Area

The Clam River is located in northwestern lower Michigan, in southeastern Wexford County. It is located in the U.S. Geological Survey's State Hydrologic Unit 04060102. Its headwaters form around Lake Cadillac and Lake Mitchell. From there, the Clam River flows in a northeasterly direction through the city of Cadillac and leaves the county about two miles north of M-55. The Clam River drains to the east and south into the Muskegon River. Part of the drainage area starts at Pleasant Lake and eventually outlets into the Clam River.

The drainage area is approximately 100 square miles with land uses of commercial, residential, recreation, agriculture, forest and open space. About 70 percent of the area is in woodland and about 10 percent is in cultivated crops. There are numerous culverts and crossings along the Clam River. Some of these are restrictive and cause the flooding of buildings and roads. Any replacement of crossings should be evaluated to see what the effect would be on downstream flooding.

There are five soil associations in the drainage area. Forty-three percent of the area consists of the Rubicon-Montcalm-Graycalm association, which has nearly level to steep, somewhat excessively drained and well drained sandy soils on moraines, till plains and outwash plains. Seven percent is the Grayling-Graycalm association, which has nearly level to moderately steep, excessively drained and somewhat excessively drained sandy soils on outwash plains, till plains and low moraines. Twenty-one percent of the area is the Kalkaska association, which has nearly level to steep, somewhat excessively drained and well drained sandy soils on outwash plains, till plains and moraines. Twenty-one percent is the Tawas-Croswell-Lupton association, which has nearly level and undulating, very poorly drained mucky and sandy soils in bogs, depressions and drainageways on low flat and benches. About two percent of the area is the Nester-Kawkawlin-Manistee association, which has nearly level to steep, well drained and somewhat poorly drained loamy and sandy soils on till plains and moraines. Lakes account for the remaining six percent of the drainage area.

In winter, the average temperature is 19.1°F., and the average daily minimum temperature is 10.9°F. In summer, the average temperature is 64.4°F., and the average daily maximum temperature is 76.7°F.

The average annual temperature is 49°F. The average annual precipitation is 30.8 inches. Of this, 18.4 inches, or 60 percent, usually falls in April through September, which includes the growing season for most crops. The average annual snowfall is 71.2 inches.

Historically, much of the watershed has been used for lumbering. Logging operations are limited to pulpwood and a small amount of timber harvested for lumber. Recreation is also a major industry.

Study Area Flood Plain

Beginning at the east county line two miles north of M-55, the study area proceeds southwesterly through the city of Cadillac, Lake Mitchell and Lake Cadillac. Part of the study area is around Pleasant Lake. High water profiles and flood plain delineations were made in Wexford County along the Clam River, as well as around Lake Mitchell, Lake Cadillac and Pleasant Lake. In addition, flood prone areas were delineated around Lake Cadillac and Lake Mitchell. The study area is identified on Figure 1.




- LEGEND**
- WATERSHED BOUNDARY
 - STUDY REACHES



VICINITY MAP

Figure No. 1
STUDY AREA MAP
CLAM RIVER
FLOOD PLAIN MANAGEMENT STUDY
 WEXFORD COUNTY, MICHIGAN



SOURCE:
 1983 GENERAL HIGHWAY MAP AND
 INFORMATION FROM SCS FIELD PERSONNEL
 POLYCONIC PROJECTION.

NATURAL VALUES

Much of the study area flood plain is wetlands. Wetland types found on National Forest within the Lake Mitchell flood plain consist of lowland brush (Type 6 USDI-Fish and Wildlife Circular No. 39); sedges, leatherleaf meadows (Type 2A); shallow and deep marshes (Types 3 and 4); bogs (Type 8); and wooded swamps (Type 7 - both conifer and hardwood). Of these wetland types, shrub swamps, bogs and wooded swamps predominate the landscape. Lowland conifers in the area include white cedar, black spruce, white pine, tamarack and balsam fir. Lowland hardwoods in the area include red maple, black ash, elm, aspen, balsam poplar and basswood. Within these types, small pockets of aspen and red maple may be found on dry ridges, often with balsam fir understories. Upland ground cover includes bunchberry, wintergreen and Lycopodium. Lowland ground cover consists of sedges, grasses, Juncus and Scirpus.

Mammals that frequent or live within the flood plain include muskrat, beaver, snowshoe hare, cottontail rabbit, red squirrel, otter, mink, weasels, skunk, red fox, deer and bear. Deer utilize much of the area as a winter deer yard because of the extensive lowland conifer types, including balsam fir on relatively dry sites. Bears probably find denning opportunities in the many windthrows in wooded lowlands. Habitat for the above species is considered good.

Birds that require mature or old growth hardwoods and conifers are found in abundance in this area. They include red-eyed vireo, pileated woodpecker, black-throated green warbler, Nashville warbler, downy and hairy woodpeckers, winter wren, white-throated sparrow, red-breasted and white-breasted nuthatches, chickadee, Eastern wood pewee and blue jay.

Birds that require or utilize shrub swamps and marshes are also common in this area. They include red-winged blackbird, yellowthroat, indigo bunting, cedar waxwing, mallard, wood duck, great blue heron, marsh wren, yellow warbler and song sparrow. There may be a heron rookery in the area. Bald eagles and ospreys are seen often, though not believed to nest in the immediate area.

Common waterfowl that may be found in migration in the flood plain and adjacent larger open waters include mute and tundra swans, American coots, a number of puddle duck and diving duck species, loons, grebes and Canadian geese.

The 100-year flood plain of Pleasant Lake includes approximately 40 acres of National Forest lands on the northwest corner of the lake. National Forest lake frontage is almost all leatherleaf bog with a scattering of tamarack. The tamarack stand becomes more dense farther from the lake and eventually grades into a mixed lowland conifer stand. This flood plain differs from that of Lake Mitchell in that there is less vegetative diversity adjacent to Pleasant Lake.

Important wildlife values of this flood plain are winter deer cover (away from the lake) and snowshoe hare habitat. Small mammal communities (shrews, voles and mice) are probably not as diverse as those found in the Lake Mitchell flood plain.

Bird communities are typical of maturing lowland conifers and include black-throated green warblers, winter wren, chickadee, red-breasted nuthatch, small woodpeckers, blue jay and white-throated sparrow. It is possible that there may be a colony of great blue herons in this flood plain or in adjacent lowland hardwoods.

There appears to be no specific data available regarding stream chemistry, however, from visual observations, the water quality of the Clam River appears to be good. The average river width is 20 feet and the fluctuating depth of flow provides aquatic habitat for several fishes and other aquatic and semi-aquatic species. The Michigan Department of Natural Resources classify the Clam River as a cool water fishery stream with species composition that includes bass, pike, sunfish, bullhead and minnows.

According to the U.S. Forest Service, there are many archaeological features in the flood plain areas. There are several prehistoric burial sites on the Lake Cadillac shoreline. Existing mounds have been identified on both north and south shores. A total of approximately 17 mounds have so far been discovered along the shore of Lake Cadillac and Lake Mitchell. Near the dam on the Clam River is the site of a prehistoric village, and evidence such as subsurface remains, pilings and other items indicate old lumber mills along both lakeshores. In addition, old campsites are present around both lakes.

FLOOD PROBLEMS

Annual flooding occurs in the early spring due to a combination of snowmelt and rainfall, and occasionally in the fall due to heavy rains.

Lake Mitchell and Lake Cadillac:

Frequent flooding occurs in areas northwest of Lake Mitchell. These areas, which are shown as flood prone areas, are located outside of and above Lake Mitchell's flood plain. Flooding occurring in flood prone areas is due to either inadequate or no road crossings or high water table soils. Drainage plans need to be developed and implemented in these flood prone areas. Although this is beyond the scope of this study, a number of recommendations are listed on page 16. The 500-year flood inundates approximately 590 acres around Lake Cadillac and Lake Mitchell. About 20 residences would experience first floor damage. In addition, approximately 1,150 acres of flood prone areas are shown within the study limits. Forty-five residences are located in these areas.

Clam River:

Flood damages are usually confined to homes and businesses along the river, particularly in the northern areas of the city of Cadillac. Some basement flooding is occurring in areas outside of the flood plain. The 100-year flood inundates approximately 220 acres. Forty-nine residences and six businesses would experience flooding during a 100-year flood.

Pleasant Lake:

Considerable flooding regularly occurs around Pleasant Lake. This is due to an inadequate outlet. The Wexford County Drain Commissioner has retained the services of an engineering firm to address this problem. The 100-year event floods approximately 120 acres. Twelve houses are flooded.

This study reports high water profiles and areas subject to flooding based on analyses of existing stream hydraulics and current watershed and flood plain land use and cover. Water surface profiles along the Clam River are plotted for the 10-, 50-, 100- and 500-year flood events. The expected extent of inundation from two floods, the 100-year and 500-year, is shown on the aerial photomaps. The photomaps indicate the approximate areas subject to flooding by the two floods, under present conditions.

To determine expected flood levels at a specific location use Sheet Index, Figure 2 (Appendix A), and refer to the appropriate Flood Hazard Photomaps to determine the location of the nearest surveyed section and the general area affected. Then, refer to the adjacent plotted high water profiles to determine the mean sea level flood elevations for that location. Profile elevations may also be used to determine the extent or depth of flooding in any given area by use of detailed field surveys.

Typical valley sections shown in Appendix B indicate the effects of the four floods. Flood discharges used for computing high water profiles in the study area are shown in Table 1 in Appendix C. Table 2 in Appendix C shows flood elevations at each of the surveyed valley sections for present conditions.

While no computations were made to reflect the problems of ice and debris blockage at bridges, because of the wide possible variations in conditions, a few generalized comments can be made. Ice and debris can often totally block an opening. To determine possible effects, look at the high water profile sheets. At each bridge or culvert, a "low point or road overflow" symbol is shown. Based on field surveys, this is the elevation at which the road would flood. If there is no culvert capacity available, all flows would need to go over the road through this low section. The depth of flow and flooding would depend on the quantity of flow, as well as cross-sectional area available for flow.

EXISTING FLOOD PLAIN MANAGEMENT

Currently, Cherry Grove, Clam Lake and Haring Townships have no existing flood plain ordinances or flood insurance. Selma Township residents became eligible for flood insurance in 1986. Flood insurance is available for residents of the city of Cadillac. An ordinance passed in 1984 sets the 100-year flood elevation of Lake Cadillac and Lake Mitchell at elevation 1291.6 feet.

ALTERNATIVES FOR FLOOD PLAIN MANAGEMENT

The objective of flood plain management is to encourage land use and development in such a manner as to minimize potential flood damage. Basic goals are to guide flood plain development consistent with the requirements of nature and the needs of the local area. Flood plain management can:

1. Prohibit uses which are dangerous to public health or safety in times of flood.
2. Restrict building or other development which may cause increased flood heights or velocities.
3. Require that public or private facilities that are vulnerable to floods be protected against flood damage at the time of construction.
4. Protect individuals from investments in flood hazard areas which are unsuited for their intended purposes.

There are numerous flood plain management alternative categories and tools that can be employed to accomplish the above objectives and goals. The ones that apply to this area are suggested below. Other flood plain management techniques should be considered and may well prove to be effective in reducing or preventing flood damages. Many of the road crossings should be resized when replacement is necessary.

Present Condition

This is the "no change" alternative which reflects ongoing flood plain development pressures and management trends. Local governmental units can continue to plan, zone and accept or reject requests for alternative flood plain and adjacent land uses. Flood problems may continue to increase if development continues.

Land Treatment

This alternative discusses opportunities to minimize or decrease changes in upland runoff and erosion because of land use changes. The traditional approach of accelerating conservation land treatment, by working with landowners to install conservation practices, will minimize soil erosion and reduce runoff. Installation of such measures as tree planting, windbreaks, forest management, permanent vegetative cover and on-site water storage will all reduce runoff, erosion and sedimentation.

As rural areas urbanize, the increase in peak discharges due to more efficient conveyance paths and increased impervious areas can have a significant adverse impact on downstream areas. There is a growing interest on the part of planners, developers and the public in protecting downstream areas from induced flood damages that may accompany increased peaks and stages. Planning authorities are proposing local ordinances that restrict the type of development permitted and the impact development can have on the watershed. One of the primary controls that could be imposed is that future-condition discharges cannot exceed present-condition discharges at some predetermined frequency of occurrence at specified points on the channel.

Methods to control runoff in urbanizing areas reduce either the volume or the rate of runoff. The effectiveness of any control method depends on the available storage, the outflow rate and the inflow rate. Because a great variety of methods can be used to control peak flows, each method proposed should be evaluated for its effectiveness in the given area.

MEASURES FOR REDUCING AND DELAYING URBAN STORM RUNOFF

Area	Reducing Runoff	Delaying Runoff
Parking Lots	<ol style="list-style-type: none"> 1. Porous pavement <ol style="list-style-type: none"> a. Gravel parking lots b. Porous or punctured asphalt 2. Concrete vaults and cisterns beneath parking lots in high value areas 3. Vegetated ponding areas around parking lots 4. Gravel trenches 	<ol style="list-style-type: none"> 1. Grassy strips on parking lots 2. Grassed waterways draining parking lot 3. Ponding and detention measure for impervious areas <ol style="list-style-type: none"> a. Rippled pavement b. Depressions c. Basins
Residential	<ol style="list-style-type: none"> 1. Cisterns for individual homes or groups of homes 2. Gravel driveways (porous) 3. Contoured landscape 4. Groundwater recharge <ol style="list-style-type: none"> a. Perforated pipe b. Gravel (sand) c. Trench d. Porous pipe e. Dry wells 5. Vegetated depressions 	<ol style="list-style-type: none"> 1. Reservoir or detention basin 2. Planting a high delaying grass (high roughness) 3. Gravel driveways 4. Grassy gutters or channels 5. Increased length of travel of runoff by means of gutters or diversions.

Preservation and Restoration of Natural Values

Flood plains, in their natural or relatively undisturbed state, provide three broad sets of natural and beneficial resources and resource values.

Water resource values include natural moderation of floods, water quality maintenance and groundwater recharge. The physical characteristics of the flood plain shape flood flows. Flood plains generally provide a broad area to spread out and temporarily store flood waters. This reduces flood peaks and velocities and the potential for erosion.

Flood plains serve important functions in protecting the physical, biological and chemical integrity of water. A vegetated flood plain slows the surface runoff, causing it to drop most of its sediment load on the flood plain. Pathogens and toxic substances entering the main water body through surface runoff and accompanying sediments are decreased.

The natural flood plain has surface conditions favoring local ponding and flood detention, plus subsurface conditions favoring infiltration and storage. The slowing of runoff provides additional time for it to infiltrate and recharge available ground water aquifers, and also provides for natural purification of the waters.

Flood plains support large and diverse populations of plants and animals. In addition, they provide habitat and critical sources of energy and nutrients for organisms in adjacent and downstream terrestrial and aquatic ecosystems. The wide variety of plants and animals supported directly and indirectly by flood plains constitutes an extremely valuable, renewable resource important to economic welfare, enjoyment and physical well-being.

The flood plain is biologically important because it is the place where land and water meet and the elements of both terrestrial and aquatic ecosystems mix. Shading of the stream by flood plain vegetation moderates water temperatures; roots and fallen trees provide instream habitat; and near stream vegetation filters runoff, removing harmful sediments and buffering pollutants, to further enhance instream environments.

Flood plains contain cultural resources important to the nation and to individual localities. Native American settlements and early cities were located along the coasts and rivers in order to have access to water supply, waste disposal and water transportation. Consequently, flood plains include most of the nation's earliest archeological and historical sites. In addition to their historical richness, flood plains may contain invaluable resources for scientific research. For example, where flood plains contain unique ecological habitats, they make excellent areas for scientific study. Flood plains may provide open space community resources. In urban communities, they may provide green belt areas to break urban development monotony, absorb noise, clean the air and lower temperatures. Flood plain parks can also serve as nature study centers and laboratories for outdoor learning experiences.

It is recommended that several selected open space areas be preserved, especially in the undeveloped areas. Their preservation, in accordance with soil limitations and good land use management, will reduce development hazards, prevent additional future flood damages and enhance the urban environment.

1. Soils with high water tables should be retained in natural vegetation. No commercial or residential construction should take place on these soils since the limitations are very severe. The Soil Conservation Service has completed a detailed soil survey of Wexford County. Copies of the material, including maps and interpretations, are available for reference in the Wexford County Soil Conservation District Office located at 3060 West 13th Street, Cadillac, Michigan 49601-9658. This information can be used to determine the kinds of soils in a given area and their limitations for various uses.
2. Upland open space should be retained in the natural state as much as possible.
3. Private wooded areas on steep slopes should be preserved from all development. Destruction of natural cover on these steep slopes usually causes excessive erosion during construction. Preservation of these wooded sites would also enhance housing developments in the area.

4. Developing areas should provide on-site flood water storage to temporarily store additional runoff volumes and peaks created by their urbanization.
5. Undeveloped flood plain areas should be managed for wildlife and recreation. These areas have potential for an excellent outdoor classroom. The Clam River is easily accessible to many school and college students.

Non-Structural Measures

1. Develop and implement, or update, a flood plain protection and zoning ordinance based on the 100-year frequency high water profile and the flood plain delineations (Appendix A). Retaining the storage in the existing flood plain area will be necessary if this flood profile is to remain valid. Reducing the storage capacity in the system will tend to increase elevations and discharges above that indicated in this report.
2. Floodproof buildings and residences already in the flood plain to reduce flood damages. Some basement windows and doors, floor drains and foundations can be modified to reduce effects of flood waters. Materials and supplies stored in vulnerable positions can be relocated and protected. These modifications can be planned and installed where it is desirable and/or feasible to continue using facilities currently in the flood plain.
3. Plans should be developed for alternate routes for auto, truck and emergency vehicle traffic around those roads that will be inundated during the flood. This will require cooperation between city, township, county and state officials.
4. Maintenance of the Clam River from the outlet at Lake Cadillac through the city of Cadillac appears to be excellent. Debris, fallen trees and brush should be removed at least yearly. Special attention should be given to the Giantway Tubes. The trash racks at the inlet should be kept free of debris at all times. Monthly cleaning is recommended. Snow and ice from road clearing operations should not be piled in the flood plain. The dam should be opened as early in the fall as possible to accommodate spring runoff.
5. Owners and occupiers of all types of buildings and mobile homes should obtain flood insurance coverage for the structure and contents, especially if located within or adjacent to the delineated flood hazard areas. The Sponsors should make necessary applications and pass needed resolutions and zoning ordinances to qualify for subsidized federal flood insurance. Contact the Land and Water Management Division, Michigan Department of Natural Resources, Mason Building, P.O. Box 30028, Lansing, Michigan 48909 for additional information.

Structural Measures

Flood stages in Lake Cadillac and Lake Mitchell could be reduced by improving flow conditions with the Clam River by increasing the channel's carrying capacity. This would require a considerable amount of channel excavation with improved bridge openings. Any attempt to reduce flood elevations around Pleasant Lake will require the construction of an outlet channel. This channel could be outleted either into the Ball Drain or rerouted to Lake Cadillac and Lake Mitchell. In any event, downstream flooding would need to be evaluated.

ALTERNATIVES FOR FLOOD PRONE AREAS

Flood prone areas northwest of Lake Mitchell, although well above the 100- and 500-year flood elevation, experience periodic flooding.

Many of the flood plain management tools discussed earlier also apply for this area. The ones that apply are mentioned below.

Present Condition

This is the "no change" alternative which reflects ongoing development pressures and management trends. Local governmental units can continue to plan, zone and accept or reject requests for adjacent land use changes. Flooding problems may continue to increase if development continues.

Preservation of Natural Areas

It is recommended that several selected open space areas be preserved, especially in the undeveloped areas. Their preservation, in accordance with soil limitations and good land use management, will reduce development hazards, prevent additional future flood damages and enhance the urban environment.

1. Soil with high water tables should be retained in natural vegetation. No commercial or residential construction should take place on these soils since the limitations are very severe.
2. Upland open space should be retained in the natural state as much as possible.
3. Developing areas should provide on-site water storage to temporarily store additional runoff volumes and peaks created by their urbanization.
4. Undeveloped flood prone areas should be managed for wildlife and recreation.

Non-Structural Measures

1. Floodproof buildings and residences already in these flood prone areas to reduce flood damages. Some basement windows and doors, floor drains and foundations can be modified to reduce effects of flood waters. Materials and supplies stored in vulnerable positions can be relocated and protected. These modifications can be planned and installed where feasible to continue using facilities currently in the flood prone area.
2. Maintenance of the Clam River from the outlet at Lake Cadillac through the city of Cadillac appears to be excellent. The maintenance should continue. In addition, the dam should be opened as early in the fall as possible. This will reduce the fluctuation of Lake Mitchell's level during spring runoff.

Structural Measures

Detailed drainage plans need to be developed for this area. Options include: a diversion around the north end of this developed area, a pump tile drainage system or a combination of the two. The services of an engineering firm will need to be retained to further investigate this potential solution.

APPENDIX A

LEGEND


- WATERSHED BOUNDARY
- 27 SHEET COVERAGE




VICINITY MAP

Figure No. 2

PHOTO SHEET INDEX
CLAM RIVER
FLOOD PLAIN MANAGEMENT STUDY
 WEXFORD COUNTY, MICHIGAN



SOURCE:
 1983 GENERAL HIGHWAY MAP AND
 INFORMATION FROM SCS FIELD PERSONNEL.
 POLYCONIC PROJECTION



VALLEY SECTIONS

ELEVATION ABOVE MEAN SEA LEVEL
IN FEET
(NATIONAL GEODETIC VERTICAL DATUM of 1929)

STUDY LIMIT

49 ROAD

LOW BANK ELEVATION


EXISTING CHANNEL BOTTOM

500-YR
100-YR
50-YR
10-YR

10.2

STATIONS ALONG CENTERLINE
IN FEET

NOTE:
Additional field measured cross-sections may be needed to verify the water surface profile between the stations used in this report. When the difference in the elevation of the channel bottom between cross-sections exceeds 2/3 the depth of flood flows, variations in the channel bottom can cause significant changes in the flood profiles.



HIGH WATER PROFILES

CLAM RIVER FLOOD PLAIN MANAGEMENT STUDY WEXFORD COUNTY, MICHIGAN			
U. S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE			
Designed <u>I. D. BOURDON</u>	Date <u>10-86</u>	Approved by _____	
Drawn <u>C. N. WADE</u>	Title <u>10-86</u>	_____	
Traced _____	Sheet _____	Drawing No _____	
Checked <u>R. H. BAUERLE</u>	Date <u>10-86</u>	No. <u>1</u> of <u>8</u>	



100 Year Flood Hazard Area

500 Year Flood Hazard Area

Flood Prone Area

Stream Channel

Valley Section Location

Channel Station

NOTE

LIMITS OF FLOODING SHOWN MAY VARY FROM ACTUAL LOCATIONS ON THE GROUND AND DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT THE PHOTOGRAPHIC WAGE MAY VARY FROM TRUE GROUND LOCATION

SCALE

0 100 200 400 600 FEET

0 100 200 METERS

APPROXIMATE

1985 NORTHERN AERIAL SURVEY PHOTOGRAPHY

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE


CLAM RIVER
FLOOD PLAIN MANAGEMENT STUDY AREA
WEXFORD COUNTY, MICHIGAN

FLOOD HAZARD AREA

CLAM RIVER

SHEET 1 OF 27

OCTOBER 1987 1000651



NOTE:
Additional field measured cross-sections may be needed to verify the water surface profile between the cross-sections used in this report. When the difference in the elevation of the channel bottom between cross-sections exceeds 2/3 the depth of flood flows, variations in the channel bottom can cause significant changes in the flood profiles.

HIGH WATER PROFILES

CLAM RIVER
FLOOD PLAIN MANAGEMENT STUDY
WEXFORD COUNTY, MICHIGAN

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Designed	T. O. BOURDON	Date	10-86	Approved by	
Drawn	C. N. WADE	Date	10-86	Title	
Traced		Date		Sheet	
Checked	R. H. BAUERLE	Date	10-86	No. 2	Drawing No.
				of 8	



100 Year Flood Hazard Area

500 Year Flood Hazard Area

Flood Prone Area

Stream Channel

Valley Section Location

Channel Station

NOTE

LIMITS OF FLOODING SHOWN MAY VARY FROM ACTUAL LOCATIONS ON THE GROUND AND DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT FROM THE PHOTOGRAPHIC IMAGE MAY VARY FROM THE GROUND LOCATION.

SCALE

0 100 200 FEET

0 100 200 METERS

APPROXIMATE

1985 NORTHERN AERIAL SURVEY PHOTOGRAPHY

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

CLAM RIVER
FLOOD PLAIN MANAGEMENT STUDY AREA
WEXFORD COUNTY, MICHIGAN


FLOOD HAZARD AREA

CLAM RIVER

SHEET 2 OF 27

VALLEY SECTIONS

ELEVATION ABOVE MEAN SEA LEVEL
IN FEET
(NATIONAL GEODETIC VERTICAL DATUM of 1929)



LOW BANK ELEVATION

EXISTING CHANNEL BOTTOM

500-YR.
100-YR.
50-YR.
10-YR.

STATIONS ALONG CENTERLINE
IN FEET

HIGH WATER PROFILES

NOTE:
Additional field measured cross-sections may be needed to verify the water surface profile between the cross-sections used in this report. When the difference in the elevation of the channel bottom between cross-sections exceeds 3/8 the depth of flood flows, variations in the channel bottom can cause significant changes in the flood profiles.

CLAM RIVER
FLOOD PLAIN MANAGEMENT STUDY
WEXFORD COUNTY, MICHIGAN

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Designed	T. D. BOURDON	Date	10-86	Approved by	
Drawn	C. N. WADE	Date	10-86	Title	
Traced		Date		Drawing No.	
Checked	R. H. BAUERLE	Date	10-86	No.	3
				of	8




NOTE
LEVELS OF FLOODING SHOWN MAY VARY
FROM ACTUAL LOCATIONS ON THE GROUND
AND DUE TO INHERENT AERIAL PHOTOGRAPHIC
DISPLACEMENTS. THE PHOTOGRAPHIC IMAGE
MAY VARY FROM TRUE GROUND LOCATION.

SCALE
0 100 200 METERS
0 400 800 FEET
APPROXIMATE

1985 NORTHERN AERIAL SURVEY PHOTOGRAPHY

- LEGEND**
- 100 Year Flood Hazard Area
 - 500 Year Flood Hazard Area
 - Flood Prone Area
 - Stream Channel
 - Valley Section Location
 - Channel Station

FLOOD HAZARD AREA	
CLAM RIVER	
U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE	
CLAM RIVER FLOOD PLAIN MANAGEMENT STUDY AREA WEXFORD COUNTY, MICHIGAN	
SHEET 3 OF 27	



NOTE:
Additional field measured cross-sections may be needed to verify the water surface profile between the cross-sections used in this report. When the difference in the elevation of the channel bottom between cross-sections exceeds 2/3 the depth of flood flow, variations in the channel bottom can cause significant changes in the flood profiles.

HIGH WATER PROFILES

CLAM RIVER
FLOOD PLAIN MANAGEMENT STUDY
WEXFORD COUNTY, MICHIGAN

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Designed	T. D. BOURDON	Date	10-86	Approved by	
Drawn	C. N. WADE	Date	10-86	Title	
Traced		Date		Sheet	4
Checked	R. H. BAUERLE	Date	10-86	of	8



100 Year Flood Hazard Area

500 Year Flood Hazard Area

Flood Prone Area

Stream Channel

Valley Section Location

Channel Station

NOTE

1. METERS OF FLOODING SHOWN MAY VARY FROM ACTUAL LOCATIONS ON THE GROUND AND DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT THE PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOCATION

SCALE 0 400 800 FEET

0 100 200 METERS

APPROXIMATE

1955 NORTHERN AERIAL SURVEY PHOTOGRAPHY

FLOOD HAZARD AREA


CLAM RIVER

FLOOD PLAIN MANAGEMENT STUDY AREA

WEXFORD COUNTY, MICHIGAN

SHEET 4 OF 27

OCTOBER 1987 1000651



NOTE:
Additional field measured cross-sections may be needed to verify the water surface profile between the cross-sections used in this report. When the difference in the elevation of the channel bottom between cross-sections exceeds 2/3 the depth of flood flows, variations in the channel bottom can cause significant changes in the flood profiles.

Bridge Deck
Road Flow
Top of C.M.P.
Invert of C.M.P.

HIGH WATER PROFILES

CLAM RIVER
FLOOD PLAIN MANAGEMENT STUDY
WEXFORD COUNTY, MICHIGAN


U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Designed	T. O. BOURDON	Date	10-86	Approved by	
Drawn	C. N. WADE	Date	10-86	Title	
Traced		Date		Scale	
Checked	R. H. BAUERLE	Date	10-86	Sheet	5 of 8



LEGEND 100 Year Flood Hazard Area 500 Year Flood Hazard Area Flood Prone Area	NOTE: LOCATIONS OF FLOODING SHOWN MAY VARY FROM ACTUAL LOCATIONS ON THE GROUND AND DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT THE PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOCATION	SCALE 0 100 200 FEET 0 100 200 METERS APPROXIMATE	FLOOD HAZARD AREA	
			CLAM RIVER	
U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE			CLAM RIVER FLOOD PLAIN MANAGEMENT STUDY AREA WEXFORD COUNTY, MICHIGAN	
SHEET 5 OF 27				

VALLEY SECTIONS



NOTE:
Additional field measured cross-sections may be needed to verify the water surface profile between the cross-sections used in this report. When the difference in the elevation of the channel bottom between cross-sections exceeds 2/3 the depth of flood flows, variations in the channel bottom can cause significant changes in the flood profile.

HIGH WATER PROFILES

CLAM RIVER FLOOD PLAIN MANAGEMENT STUDY WEXFORD COUNTY, MICHIGAN

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Designed	T.O. BOURDON	Date	10-86	Approved by	
Drawn	C.N. WAOE	Date	10-86	Title	
Traced		Date		Sheet	6
Checked	R.H. BAUERLE	Date	10-86	Drawing No.	8



100 Year Flood Hazard Area

500 Year Flood Hazard Area

Flood Prone Area

Stream Channel

Valley Section Location

Channel Station

14.0

CS50.1

0

100

200

400

600

FEET

0

100

200

400

METERS

APPROXIMATE

NOTE: VIEWS OF FLOODING SHOWN MAY VARY FROM ACTUAL LOCATIONS ON THE GROUND AND DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT. THE PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOCATION.

1985 NORTHERN AERIAL SURVEY PHOTOGRAPHY

FLOOD HAZARD AREA

CLAM RIVER

U.S. DEPARTMENT OF AGRICULTURE

SOIL CONSERVATION SERVICE


CLAM RIVER

FLOOD PLAIN MANAGEMENT STUDY AREA

WEXFORD COUNTY, MICHIGAN

SHEET 6 OF 27

OCTOBER 1987 1000651



NOTE:
Additional field measured cross-sections may be needed to verify the water surface profile between the cross-sections used in this report. When the difference in the elevation of the channel bottom between cross-sections exceeds 2/3 the depth of flood flow, variations in the channel bottom are likely to cause significant changes in the flood profiles.

Bridge Deck
Road Flow
Bridge Low Chord
Bridge Deck
Road Flow
Top of C.M.P.
Invert of C.M.P.

HIGH WATER PROFILES

CLAM RIVER
FLOOD PLAIN MANAGEMENT STUDY
WEXFORD COUNTY, MICHIGAN

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Designed	T.D. BOURDON	Date	10-86	Approved by	
Drawn	C.N. WADE	Date	10-86	Title	
Traced		Date		Sheet	7
Checked	R.H. BAUERLE	Date	10-86	of	8



LEGEND

100 Year Flood Hazard Area
500 Year Flood Hazard Area
Flood Prone Area

Stream Channel
Valley Section Location
Channel Station


14.0
CS50.1

NOTE: FLOODING SHOWN MAY VARY FROM ACTUAL LOCATIONS ON THE GROUND AND DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT THE PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOGATION.


SCALE 0 100 200 FEET
0 100 200 METERS
APPROXIMATE

1985 NORTHERN AERIAL SURVEY PHOTOGRAPHY

FLOOD HAZARD AREA	
CLAM RIVER	
U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE CLAM RIVER FLOOD PLAIN MANAGEMENT STUDY AREA WEXFORD COUNTY, MICHIGAN	
SHEET 7 OF 27	



NOTE:
 Additional field measured cross-sections may be needed to verify the water surface profile between the cross-sections used in this report. When the difference in the elevation of the channel bottom between cross-sections exceeds 2/3 the depth of flood flow, variations in the channel bottom are likely to cause significant changes in the flood profiles.



HIGH WATER PROFILES

CLAM RIVER

FLOOD PLAIN MANAGEMENT STUDY

WEXFORD COUNTY, MICHIGAN

U. S. DEPARTMENT OF AGRICULTURE

SOIL CONSERVATION SERVICE

Designed J.D. BOURDON 10-86

Drawn C.N. WAOE 10-86

Traced

Checked R.H. BAUERLE 10-86

Date 10-86

Approved by

Title

Sheet 8 of 8

Drawing No.



LEGEND

- 100 Year Flood Hazard Area
- 500 Year Flood Hazard Area
- Flood Prone Area
- Stream Channel
- Valley Section Location
- Channel Station

NOTE

LOCATIONS OF FLOODING SHOWN MAY VARY FROM ACTUAL LOCATIONS ON THE GROUND AND DUE TO "WHEREAS" AERIAL PHOTOGRAPHIC DISPLACEMENT "THE PHOTOGRAPHIC IMAGE" MAY VARY FROM TRUE GROUND LOCATION

SCALE

0 100 200 400 FEET

0 100 200 METERS

APPROXIMATE

1995 NORTHERN AERIAL SURVEY PHOTOGRAPHY

FLOOD HAZARD AREA

CLAM RIVER

CLAM RIVER

FLOOD PLAIN MANAGEMENT STUDY AREA

WEXFORD COUNTY, MICHIGAN

SHEET 8 OF 27



NOTE:
LIMITS OF FLOODING SHOWN MAY VARY
FROM ACTUAL LOCATIONS ON THE GROUND
AND DUE TO INHERENT AERIAL PHOTOGRAPHIC
DISPLACEMENT. THE PHOTOGRAPHIC IMAGE
MAY VARY FROM TRUE GROUND LOCATION.

SCALE
0 100 200 400 800 FEET
0 50 100 200 METERS
APPROXIMATE

1985 NORTHERN AERIAL SURVEY PHOTOGRAPHY

LEGEND

- 100 Year Flood Hazard Area
- 500 Year Flood Hazard Area
- Flood Prone Area
- Stream Channel
- Valley Section Location
- Channel Station

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

CLAM RIVER
FLOOD PLAIN MANAGEMENT STUDY AREA
WEXFORD COUNTY, MICHIGAN

FLOOD HAZARD AREA

CLAM RIVER

SHEET 9 OF 27



- LEGEND**
- 100 Year Flood Hazard Area
 - 500 Year Flood Hazard Area
 - Flood Prone Area
 - Stream Channel
 - Volley Section Location
 - Channel Station

NOTE: FLOODING SHOWN MAY VARY FROM ACTUAL LOCATIONS ON THE GROUND AND DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT FROM TRUE GROUND LOCATION MAY VARY FROM TRUE GROUND LOCATION

SCALE: 0 400 800 FEET
0 100 200 METERS
APPROXIMATE

1935 NORTHERN AERIAL SURVEY PHOTOGRAPHY

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
CLAM RIVER
FLOOD PLAIN MANAGEMENT STUDY AREA
WEXFORD COUNTY, MICHIGAN

FLOOD HAZARD AREA
CLAM RIVER



NOTE: FLOODING SHOWN MAY VARY FROM ACTUAL LOCATIONS ON THE GROUND AND DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT FROM PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOCATION

SCALE: 0 100 200 FEET
0 100 200 METERS
AERIAL PHOTOGRAPHY

1985 NORTH AERIAL SURVEY PHOTOGRAPHY

LEGEND

- 100 Year Flood Hazard Area
- 500 Year Flood Hazard Area
- Flood Prone Area
- Stream Channel
- 14.0
- CS50.1

FLOOD HAZARD AREA	
CLAM RIVER	
U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE	
CLAM RIVER FLOOD PLAIN MANAGEMENT STUDY AREA WEXFORD COUNTY, MICHIGAN	
SHEET 12 OF 27	



LEGEND

	100 Year Flood Hazard Area
	500 Year Flood Hazard Area
	Flood Prone Area

Stream Channel

Valley Sect on Location

CS50.1

Channel Station

SCALE

0 100 200 400 800 FEET

0 100 200 METERS

APPROXIMATE

NOTE: LIMITS OF FLOODING SHOWN MAY VARY FROM ACTUAL LOCATIONS ON THE GROUND AND DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT THE PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOCATION

FLOOD HAZARD AREA

CLAM RIVER

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

CLAM RIVER

FLOOD PLAIN MANAGEMENT STUDY AREA

WEXFORD COUNTY, MICHIGAN

SHEET 13 OF 27

OCTOBER 1987 1000651



100 Year Flood Hazard Area

500 Year Flood Hazard Area

Flood Prone Area

Stream Channel

Valley Section Location

Channel Station

LEGEND

14.0

CS50.1

SCALE

0 100 200 FEET

0 100 200 METERS

APPROXIMATE

NOTE

LIMITS OF FLOODING SHOWN MAY VARY FROM ACTUAL LOCATIONS ON THE GROUND AND DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT THE PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOCATION

1995 NORTHERN AERIAL SURVEY PHOTOGRAPHY

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

CLAM RIVER
FLOOD PLAIN MANAGEMENT STUDY AREA
WEXFORD COUNTY, MICHIGAN

FLOOD HAZARD AREA

CLAM RIVER

SHEET 14 OF 27

OCTOBER 1987 1000651



100 Year Flood Hazard Area

500 Year Flood Hazard Area

Flood Prone Area

Stream Channel

Valley Section Location

Channel Station

SCALE

0 400 800 FEET

0 200 400 METERS

1955 AERIAL PHOTOGRAPHY

NOTE: FLOODING SHOWN MAY VARY FROM ACTUAL LOCATIONS ON THE GROUND AND DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT THE PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOCATION

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

CLAM RIVER
FLOOD PLAIN MANAGEMENT STUDY AREA
WEXFORD COUNTY, MICHIGAN

FLOOD HAZARD AREA

CLAM RIVER

SHEET 15 OF 27

OCTOBER 1987 1000651



LEGEND

- 100 Year Flood Hazard Area
- 500 Year Flood Hazard Area
- Flood Prone Area
- Stream Channel
- 14.0 Valley Section Location
- CS50.1 Channel Station

NOTE: LOCATIONS OF FLOODING SHOWN MAY VARY FROM ACTUAL LOCATIONS ON THE GROUND AND DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT THE PHOTOGRAPHIC MAP MAY SHOW FLOOD BLUE GROUND LOCATION

SCALE 0 100 200 METERS
0 400 800 FEET
APPROXIMATE

1985 NORTHERN AERIAL SURVEY PHOTOGRAPHY

FLOOD HAZARD AREA

CLAM RIVER

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

CLAM RIVER
FLOOD PLAIN MANAGEMENT STUDY AREA
WEXFORD COUNTY, MICHIGAN

SHEET 16 OF 27

OCTOBER 1987 1000651



LEGEND

- 100 Year Flood Hazard Area
- 500 Year Flood Hazard Area
- Flood Prone Area
- Stream Channel
- 14.0 Year Section Location
- CS50.1 Channel Station

NOTE: LIMITS OF FLOODING SHOWN MAY VARY FROM ACTUAL LOCATIONS ON THE GROUND AND DUE TO NEPENT AERIAL PHOTOGRAPHIC DISPLACEMENT THE PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOCATION

SCALE 0 400 800 FEET
0 100 200 METERS
AERIAL PHOTO

1925 NORTHERN AERIAL SURVEY PHOTOGRAPHY

U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE		FLOOD HAZARD AREA	
CLAM RIVER FLOOD PLAIN MANAGEMENT STUDY AREA WEXFORD COUNTY, MICHIGAN		CLAM RIVER	
SHEET 17 OF 27			



LEGEND


- 100 Year Flood Hazard Area
- 500 Year Flood Hazard Area
- Flood Prone Area
- Stream Channel
- 14.0 Valley Sect or Location
- CS50.1 Channel Station

NOTE: LIMITS OF FLOODING SHOWN MAY VARY FROM ACTUAL LOCATIONS ON THE GROUND AND DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT THE PHOTOGRAPHIC IMAGE MAY VARY FROM THE GROUND LOCATION.

SCALE: 0 100 200 FEET
0 100 200 METERS

1985 NORTHERN AERIAL SURVEY PHOTOGRAPHY

FLOOD HAZARD AREA	
CLAM RIVER	
FLOOD PLAIN MANAGEMENT STUDY AREA	
CLAM RIVER	
WEXFORD COUNTY, MICHIGAN	
SHEET 18 OF 27	



LEGEND

	100 Year Flood Hazard Area
	500 Year Flood Hazard Area
	Flood Prone Area

Stream Channel

14.0

CS50.1

Channel Station

Match to Sheet

NOTE

NOTE: FLOODING SHOWN MAY VARY FROM ACTUAL LOCATION ON THE GROUND AND DUE TO "NEPENT" AERIAL PHOTOGRAPHIC DISPLACEMENT THE PHOTOGRAPHIC IMAGE MAY VARY FROM THE GROUND LOCATION

SCALE

0 100 200 300 FEET

0 100 200 METERS

APPROXIMATE

1935 NORTHERN AERIAL SURVEY PHOTOGRAPHY

FLOOD HAZARD AREA

CLAM RIVER

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

CLAM RIVER
FLOOD PLAIN MANAGEMENT STUDY AREA
WEXFORD COUNTY, MICHIGAN

SHEET 19 OF 27



100 Year Flood Hazard Area

500 Year Flood Hazard Area

Flood Prone Area

Stream Channel

Valley Section Location

Channel Station

NOTE

SCALE

1935 AERIAL PHOTOGRAPHY

100

200

300

400

500

600

700

800

900

1000

1100

1200

1300

1400

1500

1600

1700

1800

1900

2000

2100

2200

2300

2400

2500

2600

2700

2800

2900

3000

3100

3200

3300

3400

3500

3600

3700

3800

3900

4000

4100

4200

4300

4400

4500

4600

4700

4800

4900

5000

5100

5200

5300

5400

5500

5600

5700

5800

5900

6000

6100

6200

6300

6400

6500

6600

6700

6800

6900

7000

7100

7200

7300

7400

7500

7600

7700

7800

7900

8000

8100

8200

8300

8400

8500

8600

8700

8800

8900

9000

9100

9200

9300

9400

9500

9600

9700

9800

9900

10000

10100

10200

10300

10400

10500

10600

10700

10800

10900

11000

11100

11200

11300

11400

11500

11600

11700

11800

11900

12000

12100

12200

12300

12400

12500

12600

12700

12800

12900

13000

13100

13200

13300

13400

13500

13600

13700

13800

13900

14000

14100

14200

14300

14400

14500

14600

14700

14800

14900

15000

15100

15200

15300

15400

15500

15600

15700

15800

15900

16000

16100

16200

16300

16400

16500

16600

16700

16800

16900

17000

17100

17200

17300

17400

17500

17600

17700

17800

17900

18000

18100

18200

18300

18400

18500

18600

18700

18800

18900

19000

19100

19200

19300

19400

19500

19600

19700

19800

19900

20000

20100

20200

20300

20400

20500

20600

20700

20800

20900

21000

21100

21200

21300

21400

21500

21600

21700

21800

21900

22000

22100

22200

22300

22400

22500

22600

22700

22800

22900

23000

23100

23200

23300

23400

23500

23600

23700

23800

23900

24000

24100

24200

24300

24400

24500

24600

24700

24800

24900

25000

25100

25200

25300

25400

25500

25600

25700

25800

25900

26000

26100

26200

26300

26400

26500

26600

26700

26800

26900

27000

27100

27200

27300

27400

27500

27600

27700

27800

27900

28000

28100

28200

28300

28400

28500

28600

28700

28800

28900

29000

29100

29200

29300

29400

29500

29600

29700

29800

29900

30000

30100

30200

30300

30400

30500

30600

30700

30800

30900

31000

31100

31200

31300

31400

31500

31600

31700

31800

31900

32000

32100

32200

32300

32400

32500

32600

32700

32800

32900

33000

33100

33200

33300

33400

33500

33600

33700

33800

33900

34000

34100

34200

34300

34400

34500

34600

34700

34800

34900

35000

35100

35200

35300

35400

35500

35600

35700

35800

35900

36000

36100

36200

36300

36400

36500

36600

36700

36800

36900

37000

37100

37200

37300

37400

37500

37600

37700

37800

37900

38000

38100

38200

38300

38400

38500

38600

38700

38800

38900

39000

39100

39200

39300

39400

39500

39600

39700

39800

39900

40000

40100

40200

40300

40400

40500

40600

40700

40800

40900

41000

41100

41200

41300

41400

41500

41600

41700

41800

41900

42000

42100

42200

42300

42400

42500

42600

42700

42800

42900

43000

43100

43200

43300

43400

43500

43600

43700

43800

43900

44000

44100

44200

44300

44400

44500

44600

44700

44800

44900

45000

45100

45200

45300

45400

45500

45600

45700

45800

45900

46000

46100

46200

46300

46400

46500

46600

46700

46800

46900

47000

47100

47200

47300

47400

47500

47600

47700

47800

47900

48000

48100

48200

48300

48400

48500

48600

48700

48800

48900

49000

49100

49200

49300

49400

49500

49600

49700

49800

49900

50000

50100

50200

50300

50400

50500

50600

50700

50800

50900

51000

51100

51200

51300

51400

51500

51600

51700

51800

51900

52000

52100

52200

52300

52400

52500

52600

52700

52800

52900

53000

53100

53200

53300

53400

53500

53600

53700

53800

53900

54000

54100

54200

54300

54400

54500

54600

54700

54800

54900

55000

55100

55200

55300

55400

55500

55600

55700

55800

55900

56000

56100

56200

56300

56400

56500

56600

56700

56800

56900

57000

57100

57200

57300

57400

57500

57600

57700

57800

57900

58000

58100

58200

58300

58400

58500

58600

58700

58800

58900

59000

59100

59200

59300

59400

59500

59600

59700

59800

59900

60000

60100

60200

60300

60400

60500

60600

60700

60800

60900

61000

61100

61200

61300

61400

61500

61600

61700

61800

61900

62000

62100

62200

62300

62400

62500

62600

62700

62800

62900

63000

63100

63200

63300

63400

63500

63600

63700

63800

63900

64000

64100

64200

64300

64400

64500

64600

64700

64800

64900

65000

65100

65200

65300

65400

65500

65600

65700

65800

65900

66000

66100

66200

66300

66400

66500

66600

66700

66800

66900

67000

67100

67200

67300

67400

67500

67600

67700

67800

67900

68000

68100

68200

68300

68400

68500

68600

68700

68800

68900

69000

69100

69200

69300

69400

69500

69600

69700

69800

69900

70000

70100

70200

70300

70400

70500

70600

70700

70800

70900

71000

71100

71200

71300

71400

71500

71600

71700

71800

71900

72000

72100

72200

72300

72400

72500

72600

72700

72800

72900

73000

73100

73200

73300

73400

73500

73600

73700

73800

73900

74000

74100

74200

74300

74400

74500

74600

74700

74800

74900

75000

75100

75200

75300

75400

75500

75600

75700

75800

75900

76000

76100

76200

76300

76400

76500

76600

76700

76800

76900

77000

77100

77200

77300

77400

77500

77600

77700

77800

77900

78000

78100

78200

78300

78400

78500

78600

78700

78800

78900

79000

79100

79200

79300

79400

79500

79600

79700

79800

79900

80000

80100

80200

80300

80400

80500

80600

80700

80800

80900

81000

81100

81200

81300

81400

81500

81600

81700

81800

81900

82000

82100

82200

82300

82400

82500

82600

82700

82800

82900

83000

83100

83200

83300

83400

83500

83600

83700

83800

83900

84000

84100

84200

84300

84400

84500

84600

84700

84800

84900

85000

85100

85200

85300

85400

85500

85600

85700

85800

85900

86000

86100

86200

86300

86400

86500

86600

86700

86800

86900

87000

87100

87200

87300

87400

87500

87600

87700

87800

87900

88000

88100

88200

88300

88400

88500

88600

88700

88800

88900

89000

89100

89200

89300

89400

89500

89600

89700

89800

89900

90000

90100

90200

90300

90400

90500

90600

90700

90800

90900

91000

91100

91200

91300

91400

91500

91600

91700

91800

91900

92000

92100

92200

92300

92400

92500

92600

92700

92800

92900

93000

93100

93200

93300

93400

93500

93600

93700

93800

93900

94000

94100

94200

94300

94400

94500

94600

94700

94800

94900

95000

95100

95200

95300

95400

95500

95600

95700

95800

95900

96000

96100

96200

96300

96400

96500

96600

96700

96800

96900

97000

97100

97200

97300

97400

97500

97600

97700

97800

97900

98000

98100

98200

98300

98400

98500

98600

98700

98800

98900

99000

99100

99200

99300

99400

99500

99600

99700

99800

99900

100000

100100

100200

100300

100400

100500

100600

100700

100800

100900

101000

101100

101200

101300

101400

101500

101600

101700

101800

101900

102000

102100

102200

102300

102400

102500

102600

102700

102800

102900

103000

103100

103200

103300

103400

103500

103600

103700

103800

103900

104000

104100

104200

104300

104400

104500

104600

104700

104800

104900

105000

105100

105200

105300

105400

105500

105600

105700

105800

105900

106000

106100

106200

106300

106400

106500

106600

106700

106800

106900

107000

107100

107200

107300

107400

107500

107600

107700

107800

107900

108000

108100

108200

108300

108400

108500

108600

108700

108800

108900

109000

109100

109200

109300

109400

109500

109600

109700

109800

109900

110000

110100

110200

110300

110400

110500

110600

110700

110800

110900

111000

111100

111200

111300

111400

111500

111600

111700

111800

111900

112000

112100

112200

112300

112400

112500

112600

112700

112800

112900

113000

113100

113200

113300

113400

113500

113600

113700

113800

113900

114000

114100

114200

114300

114400

114500

114600

114700

114800

114900

115000

115100

115200

115300

115400

115500

115600

115700

115800

115900

116000

116100

116200

116300

116400

116500

116600

116700

116800

116900

117000

117100

117200

117300

117400

117500

117600

117700

117800

117900

118000

118100


118200

118300

118400

118500

<



NOTE
METS OF FLOODING SHOWN MAY VARY
FROM ACTUAL LOCATIONS ON THE GROUND
AND DUE TO INHERENT AERIAL PHOTOGRAPHIC
DISPLACEMENT THE PHOTOGRAPHIC IMAGE
MAY VARY FROM TRUE GROUND LOCATION


SCALE
0 100 200 METERS
0 100 200 FEET

1985 NORTHERN AERIAL SURVEY PHOTOGRAPHY


LEGEND

- 100 Year Flood Hazard Area
- 500 Year Flood Hazard Area
- Flood Prone Area
- Stream Channel
- 14.0 ft Sect on Location
- CS50.1 Channel Station

U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE		FLOOD HAZARD AREA	
CLAM RIVER FLOOD PLAIN MANAGEMENT STUDY AREA WEXFORD COUNTY, MICHIGAN		CLAM RIVER	
SHEET 21 OF 27			



LEGEND 100 Year Flood Hazard Area 500 Year Flood Hazard Area Flood Prone Area	NOTE LIMITS OF FLOODING SHOWN MAY DIFFER FROM ACTUAL LOCATIONS ON THE GROUND AND DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT THE PHOTOGRAPHIC IMAGE MAY DIFFER FROM TRUE GROUND LOCATION	SCALE 0 100 200 400 600 FEET 0 100 200 METERS AERIAL PHOTOGRAPHY 1935 NORTHERN AERIAL SURVEY PHOTOGRAPHY
FLOOD HAZARD AREA		
CLAM RIVER		
U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE CLAM RIVER FLOOD PLAIN MANAGEMENT STUDY AREA WEXFORD COUNTY, MICHIGAN		
SHEET 22 OF 27		



LEGEND

- 100 Year Flood Hazard Area
- 500 Year Flood Hazard Area
- Flood Prone Area
- Stream Channel
- Valley Section Location
- Channel Station

NOTE

LINE'S OF FLOODING SHOWN MAY VARY FROM ACTUAL LOCATION ON THE GROUND AND DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT THE PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOCATION

SCALE

0 100 200 FEET

0 100 200 METERS

1:25,000

1985 AERIAL PHOTOGRAPHY

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

CLAM RIVER

FLOOD PLAIN MANAGEMENT STUDY AREA

WEXFORD COUNTY, MICHIGAN

FLOOD HAZARD AREA

CLAM RIVER

SHEET 23 OF 27



LEGEND

- 100 Year Flood Hazard Area
- 500 Year Flood Hazard Area
- Flood Prone Area
- Stream Channel
- Valley Section Location
- Channel Station

NOTE: LOCATIONS OF FLOODING SHOWN MAY VARY FROM ACTUAL LOCATIONS ON THE GROUND AND DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT THE PHOTOGRAPHIC IMAGE MAY VARY FROM THE GROUND LOCATION.

SCALE: 1" = 400' 100' 200' 400' 800' FEET

1985 NORTHERN AERIAL SURVEY PHOTOGRAPHY

U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE		FLOOD HAZARD AREA	
CLAM RIVER FLOOD PLAIN MANAGEMENT STUDY AREA WEXFORD COUNTY, MICHIGAN		CLAM RIVER	
SHEET 24 OF 27			



100 Year Flood Hazard Area

500 Year Flood Hazard Area

Flood Prone Area

Stream Channel

Valley Section Location

Channel Station

SCALE

0 100 200 FEET

0 100 200 METERS

APPROXIMATE

NOTE

LOCATIONS OF FLOODING SHOWN MAY VARY FROM ACTUAL LOCATIONS ON THE GROUND AND DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT THE PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOCATION

LEGEND

14.0

CS50.1

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

CLAM RIVER
FLOOD PLAIN MANAGEMENT STUDY AREA
WEXFORD COUNTY, MICHIGAN

FLOOD HAZARD AREA

CLAM RIVER

SHEET 25 OF 27

OCTOBER 1987 1000651



100 Year Flood Hazard Area

500 Year Flood Hazard Area

Flood Prone Area

Stream Channel

Valley Section Location

Channel Station

14.0

CS50.1

0

100

200

300 FEET

0

100

200 METERS

SCALE

1985 NORTHERN AERIAL SURVEY PHOTOGRAPHY

FLOOD HAZARD AREA

CLAM RIVER

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

CLAM RIVER
FLOOD PLAIN MANAGEMENT STUDY AREA
WEXFORD COUNTY, MICHIGAN


SHEET 26 OF 27

NOTE

LOCATIONS OF FLOODING SHOWN MAY VARY FROM ACTUAL LOCATION ON THE GROUND AND DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT THE PHOTOGRAPHIC IMAGE MAY VARY FROM THE GROUND LOCATION

USDA/SCS NATIONAL CARTOGRAPHIC CENTER FT. WORTH TX 1987

OCTOBER 1987 1000651



100 Year Flood Hazard Area

500 Year Flood Hazard Area

Flood Prone Area

Stream Channel

Valley Section Location




Channel Station

NOTE: LOCATIONS SHOWN MAY VARY FROM ACTUAL LOCATIONS ON THE GROUND AND DUE TO AERIAL PHOTOGRAPHIC DISPLACEMENT THE PHOTOGRAPHIC MAP MAY VARY FROM THE GROUND LOCATION

SCALE 0 100 200 FEET
0 100 200 METERS
APPROXIMATE

1985 NORTHERN AERIAL SURVEY PHOTOGRAPHY

APPENDIX B



TYPICAL VALLEY SECTIONS

CLAM RIVER
FLOOD PLAIN MANAGEMENT STUDY
WEXFORD COUNTY, MICHIGAN

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Engineer	T. D. BOURDON	9-86
Designer	L. BERNARD	11-85
Checker	C. N. WADE	10-86
Reviewer	R. H. BAUERLE	10-86

APPENDIX C

.

TABLE 1 - FLOOD DISCHARGES
PRESENT CONDITIONS
Clam River

Location	TR-20 Sec.	From Sec.	To Sec.	Drainage Area Sq. Miles	Estimated Peak Discharges			
					10- Yr. -Cubic	50- Yr. Feet	100- Yr. Per	500- Yr. Second-
Lake Cadillac (Base Flow)	01			74.39	105	120	125	135
To Ann Arbor R.R.	004	24.1	22.9	74.43	115	130	140	155
To Mitchell St.	006	22.6	18.9	74.50	130	160	170	200
To Below Giantway Tubes	009	18.1	17.9	74.58	150	190	205	245
To Power St.	012	17.5	17.5	74.66	170	225	245	295
To Smith St.	015	16.1	14.8	74.81	195	275	305	375
To the Ball Drain	022	14.1	11.3	93.97	230	335	360	445
To 49 Rd.	030	11.2	10.0	99.87	230	390	460	655
Pleasant Lake	01			4.25	1	2	4	6

TABLE 2 - FLOOD ELEVATIONS AT SECTIONS
PRESENT CONDITIONS
Clam River

Location	Section	Station	10-Year	50-Year	100-Year	500-Year
Clam River						
49 Road	10.0 D	0+00	1261.3	1261.8	1261.9	1262.4
	10.0 U	0+46	1263.1	1264.4	1264.5	1264.7
	10.2	25+00	1264.2	1265.3	1265.6	1266.2
	10.3	50+00	1265.8	1266.8	1267.0	1267.7
	10.5	75+00	1267.3	1268.3	1268.7	1269.5
	10.6	100+00	1269.8	1270.7	1271.0	1271.7
	10.7	125+00	1272.5	1273.3	1273.6	1274.4
	10.8	150+00	1275.5	1276.2	1276.3	1277.0
	10.85	175+00	1278.2	1279.0	1279.2	1279.8
34 Road	10.9	184+50	1279.3	1280.0	1280.2	1280.9
	11.0 D	184+77	1279.4	1280.1	1280.3	1281.0
	11.0 U	185+23	1279.9	1281.3	1281.4	1281.7
	11.2	212+00	1281.7	1282.6	1282.9	1283.4
	11.3	240+00	1282.9	1283.6	1283.8	1284.2
Plett Road	12.0 D	271+84	1284.5	1285.0	1285.2	1285.6
	12.0 U	272+16	1284.9	1285.9	1286.3	1286.9
	12.5	273+00	1285.1	1286.1	1286.4	1287.0
13th Street	13.0 D	273+69	1285.3	1286.2	1286.5	1287.1
	13.0 U	274+31	1286.0	1287.3	1287.7	1287.9
	13.2	280+00	1286.2	1287.5	1287.9	1288.2
Smith Street	13.8	288+00	1286.6	1287.8	1288.2	1288.5
	14.0 D	291+32	1286.7	1288.0	1288.3	1288.7
	14.0 U	291+68	1286.8	1288.2	1288.4	1288.8
	14.8	299+00	1287.0	1288.4	1288.6	1288.9
Ayer Street	15.0 D	300+73	1287.1	1288.4	1288.6	1289.0
	15.0 U	301+27	1287.4	1288.7	1289.0	1289.6
	15.7	305+20	1287.5	1288.8	1289.1	1289.6
Power Street	16.0 D	307+82	1287.6	1288.8	1289.1	1289.7
	16.0 U	308+18	1287.6	1288.9	1289.2	1289.7
	17.5	314+00	1287.9	1289.1	1289.3	1289.8
Giantway Tubes	18.0 D	314+45	1287.9	1289.1	1289.3	1289.8
	18.0 U	318+45	1288.2	1289.3	1289.6	1290.2
	18.1	318+70	1288.2	1289.3	1289.6	1290.2
Mitchell St.	19.0 D	319+00	1288.2	1289.3	1289.6	1290.2
	19.0 U	319+80	1288.2	1289.4	1289.7	1290.3

TABLE 2 - FLOOD ELEVATIONS AT SECTIONS - CONTINUED
PRESENT CONDITIONS
Clam River

Location	Section	Station	10-Year	50-Year	100-Year	500-Year
NBD Parking						
Lot & R.R.	19.5 D	320+15	1288.3	1289.4	1289.7	1290.3
	19.5 U	322+15	1288.9	1289.8	1290.1	1290.8
Alpena Store	19.7 D	322+45	1288.9	1289.8	1290.1	1290.8
	19.7 U	323+15	1288.9	1289.8	1290.1	1290.8
	19.9	323+45	1288.9	1289.8	1290.2	1290.8
W. River St.	20.0 D	323+65	1288.9	1289.9	1290.2	1290.9
	20.0 U	324+25	1288.9	1289.9	1290.2	1290.9
Lake Street	21.0 D	326+41	1289.1	1290.0	1290.2	1290.9
	21.0 U	326+79	1289.2	1290.0	1290.3	1291.0
	21.6	330+50	1289.2	1290.0	1290.3	1291.0
Ann Arbor R.R.	22.0 D	331+46	1289.2	1290.1	1290.3	1291.0
	22.0 U	331+64	1289.3	1290.3	1290.6	1291.3
	22.6	336+80	1289.5	1290.3	1290.6	1291.3
Haynes Street	23.0 D	340+73	1289.6	1290.4	1290.7	1291.3
	23.0 U	341+37	1289.6	1290.4	1290.7	1291.3
	23.6	345+70	1289.8	1290.5	1290.7	1291.4
Dam	23.65	345+85	1289.8	1290.5	1290.7	1291.4
	23.7	346+10	1289.8	1290.5	1290.7	1291.4
Chestnut St.	24.0 D	348+33	1290.1	1290.7	1290.9	1291.5
	24.0 U	349+07	1290.4	1290.9	1291.1	1291.7
Lake Cadillac and Lake Mitchell			1290.8	1291.2	1291.4	1291.7
Pleasant Lake			1329.0	1329.4	1329.5	1329.6

APPENDIX D

Survey Procedures

Field surveys were made of bridges, roads, structures, channels and flood plains around Lake Cadillac and Lake Mitchell by the Soil Conservation Service in 1985 and around Pleasant Lake in 1986. Temporary bench marks based on USC & GS mean sea level elevations data of 1929 were also set at this time and used for this study. In addition, several temporary bench marks, previously set by the city of Cadillac were used. Surveys were made using second order accuracy. Temporary bench marks are described in Appendix E.

For the Clam River, 18 valley and channel cross-sections plus 22 roads, bridges and structures were surveyed. Eight shoreline cross-sections were surveyed around Lake Cadillac and Lake Mitchell. Eight shoreline cross-sections were surveyed around Pleasant Lake. Six valley and channel cross-sections plus two roads and bridges were surveyed for Pleasant Lake. Aerial photography flown on April 28, 1985 was used as a base for the photo mosaic sheets used to delineate the flood plains. U.S. Geologic Survey topographic maps and two foot contour maps provided by the city of Cadillac were used to extend valley cross-sections.

Hydrology and Hydraulics

Physical data were obtained from U.S.G.S. topographic maps, soil survey maps, local topographic maps and aerial photographs, as well as on-site field inspections. The watershed boundary was determined from map studies and field checks. The watershed was divided into 13 sub-watershed areas for use in evaluating the runoff volumes. Drainage areas for the sub-watersheds were measured from U.S.G.S. topographic maps. Times of concentration were calculated for the sub-watersheds using the upland flow method. Each sub-watershed was evaluated for land use, cover and soils. Runoff curve numbers were calculated.

Due to considerable differences in sub-watersheds, travel times, time of concentrations, soil conditions and topography, the analyses consist of three parts: 1) Lake Mitchell and Lake Cadillac, 2) Clam River and 3) Pleasant Lake.

Lake Mitchell and Lake Cadillac:

The lakes were treated as one body of water. The drainage area above the lakes is approximately 75 square miles; however, the area that contributes surface runoff is only about 46 square miles. The soils are very sandy and pervious with considerable vegetative cover. Many of the roads prevent surface runoff from directly entering the lakes. In addition, several of the smaller lakes and swamps above Lake Mitchell and Lake Cadillac are landlocked. Therefore, a surface water analysis alone would not be adequate. Snowmelt and groundwater needed to be included.

Information from U.S.G.S. stream gage No. 04121300 located at Vogel Center was utilized to develop information for the TR-20 flood routing program used to determine elevations and peak discharges out of the lakes. Inflow hydrographs into the lakes were developed based on a volume-duration-probability analyses of the gage and the area above the lakes. Outflow hydrographs were based on elevation-discharge relationships developed by the WSP-2 water surface profile program and storage calculations. Daily lake elevation records from the U.S.G.S. staff gage located at Lake Cadillac, along with Weather Bureau data, were used to determine a starting lake elevation of 1290.5, which was used to model existing conditions. The TR-20 computer program used the Storage Indication method of evaluating the affect of the lakes in reducing peak flood discharges into the Clam River. Table 1 (Appendix C) lists discharges obtained from the flood routings and Table 2 (Appendix C) lists lake elevations.

Information from the U.S.G.S. staff gage located at Lake Cadillac was used to verify the peak lake elevations. A frequency analysis using a Weibull plot very closely approximates peak elevations as determined by the TR-20 model.

Clam River:

Channel flood routings to establish peak discharge-frequency relationships were made using the SCS TR-20 Hydrology Computer Program and U.S. Department of Agriculture computer facilities. The Modified Attenuation-Kinematic (Att-Kin) method of routing through stream channels is used by this program. This method is derived from inflow-outflow hydrograph relationships.

Base flood flows from Lake Cadillac and Lake Mitchell, local runoff and valley sections were used to flood route and model study area conditions. Table 1 (Appendix C) lists discharges obtained from the flood routings and Table 2 (Appendix C) lists flood elevations at sections.

Information from the U.S.G.S. stream gage at Vogel Center and U.S.G.S. Water Supply Paper 1677 were used to verify peak discharges at the county line as determined by the TR-20 model. Peak discharges for the 100-year flood compared within 4 percent.

Pleasant Lake:

The Pleasant Lake drainage area is approximately 4.25 square miles. Flood waters from Pleasant Lake flow to the south under Road No. 32 and eventually enter Lake Cadillac and Lake Mitchell. The hydrology and hydraulics analysis was similar to Lake Cadillac and Lake Mitchell.

Inflow hydrographs into the lake were developed based on a volume-duration-probability analysis of the U.S.G.S. stream gage at Vogel Center. Outflow hydrographs for discharge out of the lake were based on elevation-discharge relationships developed by the WSP-2 water surface profile program and TR-20 flood routing program. A starting lake elevation of 1326.80 feet was used to model existing conditions. Table 1 (Appendix C) lists discharges obtained from the flood routings and Table 2 (Appendix C) lists lake elevations.


Water surface profiles for the Clam River and Pleasant Lake outlet channel were developed using the Soil Conservation Service WSP-2 computer program. This program uses the step method of computation to solve the Bernoulli equation, and the Bureau of Public Roads bridge loss analysis. Flood discharges determined from flood routings were used in the water surface profile program to develop high water profiles along the Clam River and Pleasant Lake outlet channel. Mannings "n" values were determined from field investigations of the channels and flood plains.

Normal bridge and channel flow conditions were assumed in the hydraulic computations. No consideration was made for openings blocked by ice or other debris. Channel and flood plain flow characteristics may change due to vegetative growth, sedimentation, scour, debris accumulation, filling and encroachment. Computations for this study considered only those features in the flood plain at the time of field surveys. Future flood plain developments and modifications, as well as changes in the upstream drainage area and land use and cover will require recomputation of water surface profiles.

Flood plain delineations were made on the contour maps and photo map sheets. Computed water surface elevations at surveyed sections and bridges were used to identify flood plain limits. Between sections, topographic map interpretations and field inspections were used to delineate the flood boundary lines. Limits of flooding shown on the photo maps may vary from actual location on the ground and the photographic image may vary from true ground location due to inherent aerial photographic displacement. Flood plain delineations around Lake Cadillac and Lake Mitchell were based on the computed lake level. Wave action may cause flooding of additional areas. In addition, road fills with inadequate or no crossings and high water table soils are causing some flooding above the roads. These areas were delineated as flood prone areas in this study. In most cases, these areas are above the 500-year and 100-year flood elevations. Detailed soil borings should be conducted in these areas in the event of possible development. High water profile elevations and detailed field surveys should be used to determine the extent or depth of flooding at any specific site.

Where the limits of the 500-year and 100-year floods were too close to delineate, the limits of the two flood plains are shown as the same line on the flood hazard area sheets.

APPENDIX E



CITY OF CADILLAC
DETAIL

Approximate Scale in Feet

LEGEND

- TOWNSHIP LINE
- T.B.M. 231B BENCH MARK



VICINITY MAP

BENCH MARK LOCATION MAP
CLAM RIVER
FLDDD PLAIN MANAGEMENT STUDY
PORTIONS OF
WEXFORD COUNTY, MICHIGAN

Approximate Scale in Miles

Material prepared by David Perumal. Reproduction
only by U.S. Cartographic Staff, Fort Worth, Texas

BENCH MARK DESCRIPTIONS *

CLAM RIVER

WEXFORD COUNTY, MICHIGAN

BM 70B

Section 24, T22N, R9W - Railroad spike in south side of power pole located 75 feet west of Missaukee County Line Road also known as 49 Road and 80 feet south of the Clam River.

Elev. 1269.27

BM 65B

Section 24, T22N, R9W - Top of iron in concrete marker located 50 feet northwest of the intersection of Boon Road and Sarah Street.

Elev. 1286.06

BM 62B

Section 23, T22N, R9W - Railroad spike in south side of power pole located near section line common to sections 23 and 24. The power pole is the first power pole south of the Clam River.

Elev. 1273.38

BM 60B

Section 23, T22N, R9W - Railroad spike in the north side of power pole located 65 feet northwest of the south 1/16 corner of southeast 1/4 of section 23.

Elev. 1287.14

BM 55B

Section 22, T22N, R9W - Railroad spike in the south side of power pole, located on the north side of Boon Road and being the first power pole west of the Clam River and Boon Road intersection.

Elev. 1283.24

BM 50

Section 27, T22N, R9W - Railroad spike in west side of power pole, southeast of the junction of Boon Road and Plett Road.

Elev. 1285.59

* Elevations based on USC & GS mean sea level datum of 1929.

BM 42

Section 34, T22N, R9W - Railroad spike in north side of power pole located at the southeast corner of the intersection of Platt Road and 13th Street.

Elev. 1288.63

BM 144

Section 33, T22N, R9W - Railroad spike in power pole at the south side of Ford Street at the intersection of Ford, Dandy and Riverside Street.

Elev. 1289.34

BM 146

Section 33, T22N, R9W - Railroad spike in guy pole at the southwest corner of Ayer and Wheeler Streets.

Elev. 1293.34

BM 73

Section 33, T22N, R9W - Top of steamer valve on fire hydrant located at the northwest corner of Powers and Baker Streets.

Elev. 1291.10

BM 78

Section 33, T22N, R9W - Top of steamer valve on fire hydrant located in the southerly corner of Wheeler Street and North Simmons Street.

Elev. 1294.26

TBM 780B

Section 33, T22N, R9W - Top of the northeast corner of the fourth concrete guardrail pillar to the north located on the east side of U.S. 131 at Giantway.

Elev. 1294.71

BM 140

Section 33, T22N, R9W - Chisled mark on top of safety rail at the northwest corner of the Clam River Bridge near Novak Building.

Elev. 1295.12

BM 145B

Section 33, T22N, R9W - Top of steamer valve on fire hydrant located southeast of the corner of West River Street (Wright) and Second Ave.

Elev. 1295.45

TBM 140B

Section 33, T22N, R9W - "X" chisled in top of square steel rod at the north-east corner of Wood Railroad Tressel located in the northwest corner of the Ann Arbor railroad and Clam River intersection. 550 feet southwest of the intersection of Lake Street and West River Street (Wright).

Elev. 1290.75

BM 39

Section 33, T22N, R9W - South bolt on fire hydrant located east of the intersection of Bond and Haynes Street.

Elev. 1294.02

BM DAM

Section 33, T22N, R9W - "X" chiseled on top of southwest corner of concrete abutment of the Clam River Dam at Consumers Power.

Elev. 1292.07

TBM 1-36

Section 1, T21N, R10W - Spike in power pole located in front of House No. 917 North Lake Mitchell Drive.

Elev. 1293.43

TBM 1-39

Section 1, T21N, R10W - Spike in power pole opposite 477 North Lake Mitchell Drive.

Elev. 1294.72

BM 61

Section 6, T21N, R9W - Spike in the west side of power pole located northeast of the intersection of M-115 and North Blvd.

Elev. 1302.34

BM 61B

Section 6, T21N, R9W - Railroad spike in south side of power pole No. 505 located on the north side of North Boulevard 720 feet east of M-115.

Elev. 1293.27

BM 169

Section 7, T21N, R9W - Railroad spike in power pole at the westerly corner of the intersection of M-55 and S. Lake Mitchell Drive of Cadillac West Motel.

Elev. 1296.44

TBM 2-26

Section 12, T21N, R10W - Spike in north root of 20 inch diameter red oak south side of M-55 at Caberfac Motor Inn.

Elev. 1299.96

BM B1

Section 12, T21N, R10W - Split "I" on top of northeast edge of Bell Systems manhole cover rim located in northerly corner of M-55 and Pole Road Junction.

Elev. 1295.91

TBM 2-15

Section 10, T21N, R10W - Chiseled "X" in top square of triangular concrete post, 15 feet west and 25 feet south of Sunset Pt. Road (33 Mile Road) at the intersection of South Lake Mitchell Drive and 33 Mile Road.

Elev. 1299.40

TBM 2-2

Section 10, T21N, R10W - Spike in east side of 20 inch poplar tree 50 feet south and 25 feet west of the intersection of Sunset Point Road and Woodland Drive.

Elev. 1297.66

BM 220B

Section 10, T21N, R10W - Railroad spike in north side of power pole at the south side and end of 33 Road at Sunset Point Cabins.

Elev. 1293.07

TBM 230B

Section 10, T21N, R10W - Railroad spike in north side of power pole located in the southeast corner of the intersection of South Lake Mitchell Drive (Pole Road) and South 31 Road.

Elev. 1301.25

TBM 231B

Section 9, T21N, R10W - Railroad spike in east side of 12 inch diameter maple tree located on the west side of 31 Road, 0.25 miles north of Pole Road.

Elev. 1297.16

TBM 1-1

Section 3, T21N, R10W - Spike in power pole south of House No. 519 Lake Drive.

Elev. 1295.33

TBM 1-8

Section 34, T22N, R10W - Spike in power pole on south side of North Lake Mitchell Drive at House No. 4301.

Elev. 1294.34

TBM 1-15

Section 35, T22N, R10W - Spike in power pole at west side of House No. 3367 North Lake Mitchell Drive.

Elev. 1292.30

BM B7

Section 26, T22N, R10W - Top of cap on cement marker reading "Wexford County Board of Public Works" located 75 feet east and 50 feet north of the intersection of North Lake Mitchell Drive and Ann Arbor railroad tracks.

Elev. 1296.87

BM B8

Section 25, T22N, R10W - Top northeast corner concrete marker, "Wexford County Board of Public Works", located 45 feet north and 35 feet east of the intersection of East Lake Mitchell Drive and Ann Arbor railroad tracks.

Elev. 1305.93

BM B9

Section 25, T22N, R10W - Top of the northwest bolt of the railroad warning light base, located in the southeast corner of the intersection of M-115 and Ann Arbor railroad tracks.

Elev. 1307.25

BM 13

Section 22, T22N, R10W - 2 miles north and 6 miles west of Cadillac, 27 feet north and 35 feet east of crossroads, 12 feet east of corner post, in concrete post, standard tablet stamped "TT 112 TEX 1930 1353".

Elev. 1353.06

BM LJ 105

Section 14, T22N, R10W - Top of nail set 0.5 feet above ground, south side of power pole, 39 feet north of Rd. No. 32, 419 feet east of the intersection of 35 Rd. and Rd. No. 32 at No. 5095.

Elev. 1335.17

BM LJ 107

Section 13, T22N, R10W - Top of nail set 6 inches up from ground on west side of power pole, east side of Lake Shore Drive and south side of drive to Richardsons at No. 2753 Lake Shore Drive.

Elev. 1331.42

BM LJ 109

Section 13, T22N, R10W - Top of nail set 6 inches up from ground on west side of power pole, 39 feet east of 35 1/2 Road, and 178 feet north of intersection of Lake Shore Drive and 35 1/2 Road.

Elev. 1338.61

APPENDIX F

GLOSSARY

BACKWATER--The resulting highwater surface upstream from a dam, bridge or other obstruction in a river channel or high stages in a receiving stream.

BRIDGE DECK--Elevation of road surface at the bridge.

BRIDGE LOW CLEARANCE--The lowest point of a bridge or other structure over or across a river, stream or water course that limits the opening through which water flows. This is referred to as "low steel" or "low chord". It often is higher than the low point of the roadway.

CHANNEL or WATER COURSE--An elongated depression either natural or man-made having a bed and well-defined banks varying in depth, width and length which gives direction to a current of water and is normally described as a creek, stream or riverbed.

CHANNEL BOTTOM--The lowest part of the stream channel (either in a constructed cross-section or a natural channel). Bottom elevations at a series of points along the length of a stream may be plotted and connected to provide a stream bottom profile.

CONFLUENCE--A flowing together or place of junction of two or more streams.

CROSS-SECTION or VALLEY SECTION--A graph showing the shape of the stream bed, banks and adjacent land on either side made by plotting elevations at measured distances along a line perpendicular to the flow of the stream.

DATUM--An assumed reference plane from which elevations and depths are measured such as from sea level.

ELEVATION-DISCHARGE RELATIONSHIP--The relationship between water surface elevation and rate of flow at a specified location for a range of flow rates.

FLOOD--A temporary overflow by a river, stream, ocean, lake or other body of lands not normally covered by water. It does not include the ponding of surface water due to inadequate drainage such as within a development. It is characterized by damaging inundation, backwater effects of surcharging sewers and local drainage channels, and by unsanitary conditions within adjoining flooded habitated area attributable to pollutants, debris and water table.

FLOOD CREST--The maximum stage or elevation reached by flood waters at a given location.

FLOOD FREQUENCY--A means of expressing the probability of flood occurrences as determined from a statistical analysis of representative stream flow or rainfall and runoff records. It is customary to estimate the frequency with which specific flood stages or discharges may be equaled or exceeded, rather than the frequency of an exact stage or discharge. Such estimates by strict definition are designated "exceedence frequency", but in practice the term "frequency" is used. The frequency of a particular stage or discharge is usually expressed as occurring once in a specified number of years.

10-YEAR FLOOD--A flood having a long-term average frequency of occurrence in the order of once in 10 years. It has a ten percent chance of being equaled or exceeded in any given year.

100-YEAR FLOOD--A flood having a long-term average frequency of occurrence in the order of once in 100 years. It has a one percent chance of being equaled or exceeded in any given year. This flood is comparable to the "Intermediate Regional Flood" used by the U.S. Army Corps of Engineers.

FLOOD PEAK--The maximum instantaneous discharge or volume of flow in cubic feet per second passing a given location. It usually occurs at or near the time of the flood crest.

FLOOD PLAIN--The relatively flat area or low lands covered by flood waters originating with either the adjoining channel of a water course such as a river or stream, or a body of standing water such as an ocean or lake.

FLOOD PRONE AREA--Areas that experience ponding due to high water table soils and/or inadequate outlets.

FLOOD ROUTING--The process of determining progressively the timing and shape of a flood wave at successive points along a stream. This procedure is used to derive a downstream hydrograph from an upstream hydrograph. Local inflow and tributary hydrographs are considered.

FLOOD STAGE--The elevation at which overflow of the natural stream banks or body of water occurs.

FLOODWAY--The portion of the flood plain including the channel of the stream that is required for the conveyance of flood flow.

FLOODWAY FRINGE--The area of the flood plain lying outside the floodway which may be covered by flood waters originating from an adjoining river or stream.

HEAD LOSS--The effect of obstructions, such as narrow bridge openings, dams or buildings, that limit the area through which water must flow, raising the surface water upstream from the obstruction.

HEADWATER--The tributaries and upper reaches which are the sources of the stream.

HIGH WATER or FLOOD PROFILE--A graph showing the relationship of water surface elevation location along the stream. While it is drawn to show surface elevations for the crest of a specific flood, it may be prepared for conditions at any other given time or stage.

HYDRAULICS--The science of the laws governing the motion of water and their practical applications.

HYDROGRAPH--A graph denoting the discharge or stage of flow over a period of time.

HYDROLOGY--The science dealing with the occurrence and movement of water upon and beneath the land areas of the earth.

INUNDATION--The flooding or overflow of an area with water.

LEFT BANK--The bank of the left side of a river, stream or water course, looking downstream.

LOW GROUND--The highest elevation at a specific stream channel cross-section at which the flow in the stream can be contained in the channel without overflowing into adjacent overbank areas.

MANNING'S "n"--A coefficient of channel and overbank roughness used in Manning's open channel flow formula, commonly called a retardance factor.

REACH LENGTH--A longitudinal length of stream channel selected for use in hydraulic or other computations.

RIGHT BANK--The bank on the right side of the river, stream or water course, looking downstream.

ROAD OVERFLOW--The lowest elevation on a road profile in the vicinity of where the road and stream cross. It is the first point on the roadway inundated if overtopping of the road occurs during a storm.

RUNOFF--That part of precipitation, as well as any other flow contributions, which appears in surface streams of either perennial or intermittent form.

TIME OF CONCENTRATION--Time required for water to flow from the most remote point of a watershed to the outlet or other point of reference.

WATERSHED--A drainage basin or area which collects runoff and transmits it, usually by means of streams and tributaries, to the outlet of the basin.

WATERSHED BOUNDARY--The divide separating one drainage basin from another.

APPENDIX G

BIBLIOGRAPHY

- Michigan Department of Agriculture, Climate of Michigan by Stations, Michigan Weather Service, East Lansing, Michigan, 1974.
- State of Michigan, Flood Plain Regulatory Authority, Act of 1968, Act 245, P.A. 1928 as amended by Act 167, P.A. 1968, Michigan Water Resources Commission, Lansing, Michigan, 1967.
- State of Michigan, Subdivision Control Act of 1967, Act 288, P.A. 1967 as amended, Michigan Water Resources Commission, Lansing, Michigan, 1967.
- U.S. Army, A Perspective on Flood Plain Regulations for Flood Plain Management, Corps of Engineers, Washington, D.C., 1976.
- U.S. Army, Guidelines For Reducing Flood Damages, Corps of Engineers, Vicksburg, Mississippi, 1967, 12 pp.
- U.S. Department of Agriculture, Soil Survey of Lake and Wexford Counties, Michigan, Soil Conservation Service, East Lansing, Michigan, August 1985.
- U.S. Department of Agriculture, Urban Hydrology For Small Watersheds, Technical Release No. 55, Soil Conservation Service, Washington, D.C., 1986.
- U.S. Water Resources Council, Regulation of Flood Hazard Areas To Reduce Flood Losses, Volumes 1 and 2, U.S. Water Resources Council, Washington, D.C., 1971 and 1972, 967 pp.
- U.S. Water Resources Council, A Unified National Program for Flood Plain Management, Washington, D.C., September 1979, 98 pp.
- U.S. Department of Agriculture, National Engineering Handbook, Section 4, Hydrology, Soil Conservation Service, Washington, D.C., 1972.
- U.S. Department of Agriculture, Computer Program For Project Formulation - Hydrology, Technical Release No. 20, Soil Conservation Service, Washington, D.C., May 1982.
- U.S. Department of Agriculture, WSP2 Computer Program, Technical Release No. 61, Soil Conservation Service, Washington, D.C., 62 pp.
- U.S. Department of Interior, Statistical Models for Estimating Flow Characteristics of Michigan Streams, U.S. Geological Survey, Washington, D.C., Draft dated 1983, D. J. Hochtshlag and H. M. Croskey.
- U.S. Department of Agriculture, Hydrology Study - A Multipurpose Program for Selected Cumulative Probability - Distribution Analysis, Technical Paper 148, Soil Conservation Service, Washington, D.C., September 1963.

